

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/22/2014

CORNER DESIGNATION: J-21.8, MP40, Township 6 North, Range 36E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by Daniel G Major in 1864, built stone mound and marked stone slab on top "40M" "1864" 46°L from which a large Pine marked "W" bears N86°E distance 2 chains, one of two dried firs marked "O" bears S77°30'E 60 links, a 2 foot diameter pine bears S22°W, distance 3 chains, a pine 2 foot in diameter bears N48°W distance 65 links.

BLM Cadastral Surveyor Richard L. Johnson in 1991 found the remains of an original bearing tree and set a 2 ½" x 28" stainless steel post with a 3" brass cap S86°W 200 links (132.0 feet) from the found original bearing tree from which he marked a 17 inch diameter Ponderosa Pine S3 ¼°W 91 ½ links marked 40M ORE BT.

MOUNUMENT AND ACCESSORIES FOUND:

Found 3 ¼ inch BLM brass cap on a 2 ½ inch stainless steel pipe in a mound of stone. From which a 20 inch diameter Ponderosa Pine with a healed blaze and bearing tree sign. Bears S3¼°W 60.4 feet

MOUNUMENT MARKING DETAIL:

40M
WASHINGTON
OREGON
1991

MOUNUMENT AND ACCESSORIES SET:

A 12 inch diameter Ponderosa Pine bears S15½° E 56.1 feet marked 40M ORE BT

A 20 inch diameter pine bears N19½° 35.3 feet marked 40M WA BT

A nail and brass washer and bearing tag set on the face of a rock outcropping bears N29°E 7.3 feet.

LOCATION AND COMMENTS:

The 40 mile post on the Oregon and Washington boarder. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859692.04

E = 8802018.43

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F. Wendover
Felipe G. Hernandez

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015