

**OREGON CORNER RESTORATION FORM**

**COUNTY:** Umatilla    **DATE:** 2/13/2015

**CORNER DESIGNATION:** R-17, Section Corner common to Sections 22, 23, 27 and 26 Township 6 North, Range 37 East, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by George Williams, Contract No. 176, dated July 20, 1872. His notes state "Set stone in mound 7 x 12 x 10 for corner to Sec 22, 23, 26 and 27.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found.

**MOUNUMENT MARKING DETAIL:**

LS 02820  
T6N R37E  
S22 | S23  
S27 | S26  
2015

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set a 2½" brass cap on 1½" x 30" galvanized iron pipe projecting 6" above ground on NW facing slope in brush 6.00 – 10.00 ft. tall at bottom of medium canyon with 6.00 ft. "T" post and sign – 2.00 ft. North, from which set:

- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N26°E, 10.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N81°E, 13.50 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S37°E, 10.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S65°W, 17.00 feet distance.

**LOCATION AND COMMENTS:**

Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**


N = 851204.97  
E = 8795768.59

**COMPASS DECLINATION:** 15° East

**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Joseph R. Latimer  
Cory A. West



RENEWS 12/31/15

06/29/2015