

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/21/2014

CORNER DESIGNATION: R-23, Quarter Corner Section for Sections 24 and 25, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams in 1872 his notes state "Set post for quarter section corner to Sections 24 & 25 in a mound with pits."

MOUNUMENT AND ACCESSORIES FOUND:

No Evidence Found

MOUNUMENT MARKING DETAIL:

1/4 $\frac{T6N}{\frac{S24}{S25}}$ R37E
2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" galvanized iron pipe with a 2½" brass cap marked as shown on East facing grassy slope, built mound 24" diameter x 8" high. Top of cap stands 12" above ground above surface. Set a post with tag 1.00 feet N, from which:

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N67°W, 32.15 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S46½°W, 35.30 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S64°E, 25.00 feet.

A 24 inch in diameter Pine, bears N68°E, 88.10 feet, blazed, scribed and tagged.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 851300.18


E = 8803686.80

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F. Wendover
Felipe G. Hernandez



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015