

MOUNUMENT AND ACCESSORIES FOUND:

Found a 2½” pipe with ¾” BLM brass cap,
A 22” fir with scribe, blazed and tag bears S 15°W, 9.00’
A 25” fir with scribe, blazed and tag bears N 74¼°W, 18.00’
A 23” ponderosa pine with blaze, scribe, and tag bears S 70½°W, 122.40”
Surveyor Wayne O. Harris noted in his June 27, 1961 survey, shown on Umatilla County Survey, record of surveys 03-291-A (Drawing Number 61-112-C), “Set steel stake 16” D. fir E-25.1; 22” D. fir S66°W-8.5; 10” D. fir N48°W-11.7”

MOUNUMENT MARKING DETAIL:



MOUNUMENT AND ACCESSORIES SET:

From above referenced monument:
A 14 inch diameter White fir, N33½°W, 22.90 feet, blazed, scribed and tagged. Bearing tag marked T6N R37E S24 BT.

LOCATION AND COMMENTS:

Point is on a hogback running NE from the top of ridge which is 170’ SW. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 851342.56
E = 8806313.39

COMPASS DECLINATION: 15° East

SURVEYORS’ SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F. Wendover
Felipe G. Hernandez



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 5/21/2014

CORNER DESIGNATION: R-25, Corner for Sections 24 and 25, Township 6 North, Range 37E, Sections 19 and 30, Township 6 North, Range 38E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865, their note states "Marked corner on Fir 4 inches in diameter for sections 19, 30, 24 and 25, in thick growth of fir timber on steep hill side facing the N East, from which:

A Fir 4 inches in diameter, bears S40°W, 6 links.

A Fir 8 inches in diameter, bears S50°E, 5 links.

A Fir 4 inches in diameter, bears N20°W, 10 links.

A Fir 3 inches in diameter, bears N10°E, 8 links.

Surveyor Wayne O. Harris noted in his June 27, 1961 survey, shown on Umatilla County Survey, record of surveys 03-291-A (Drawing Number 61-112-C), "Set steel stake, 16" Douglas fir E – 25.1, 22" Douglas fir S66°W–8.5 and 18" Douglas fir N48°W–11.7."

Per the United States Department of the Interior Bureau of Land Management Survey and notes dated June 25, 1993, and executed by Richard L. Johnson, Phillip G. Griffin, Larry D. Holmes and Richard R. Shatto, Cadastral Surveyors, beginning October 13, 1987 and completed September 16, 1991 pursuant to Special instruction dated September 18, 1987 and Supplemental Special Instructions dated May 9, 1990, under Group Number 1405, Oregon, there notes state "Point for the cor. of secs. 19, 24, 25 and 30, at proportionate distance; there is no remaining evidence of the original corner. Set a stainless steel post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, and in a collar of stone, with a brass cap mkd.

T6N
R37 E R38E
S 24 | S 19
S 25 | S 30
1991

From which:

A ponderosa pine, 19 ins. diam., bears S. 70½° E., 185½ lks. dist., mkd. T6N R38E S19 BT.

A fir, 22 ins. diam., bears S. 59° E., 88 lks. dist., mkd. T6N R38E S30 BT.

A fir, 24 ins. diam., bears S. 23¼° W., 14 lks. dist., mkd. T6N R37E S25 BT.

A fir, 26 ins. diam., bears N. 74¼° W., 29 lks. dist., mkd. T6N R37E S24 BT.

Deposit a white "DEEP-1" magnetic marker at base of stainless steel post.

The corner is located in timber and undergrowth.

From this point, a point reestablished as the cor. Of secs. 19, 24, 25 and 30, recorded by Wayne O. Harris, Registered Land Surveyor No. 346 in 1960, in the Umatilla County Surveyor's Office bears N. 69° 51'00"W., 1.630 chs. dist., monumented with an iron rod, 1 in. square, firmly set 18 ins. below ground. This point is not properly positioned and is not utilized in this survey, from which the remains of bearing trees mkd. by Harris:

A fir stump, 26 ins. diam., bears S. 8½° E, 39 lks. dist., no marks.

A fir stump, 31 ins. diam., bears S. 73¾° W, 12½ lks. dist., with illegible scribe marks on partially healed blaze.

A fir stump, 32 ins. diam., bears N. 49¾° W, 19 lks. dist., no marks on partially healed blaze.