


COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Mark F. Wendover  
Felipe G. Hernandez

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/15

06/29/2015

## OREGON CORNER RESTORATION FORM

COUNTY: Umatilla      DATE: 07/22/2014

**CORNER DESIGNATION:** T-21, Quarter Corner Section for Sections 26 and 25, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post for quarter section corner for Sections 26 & 25, from which a Tamarac 12 inch diameter bears N10°W 65 links distance, a fir 8 inch diameter bears S20°E 20 links distance.

Surveyor Paul W.P. Tomkins noted in his February 15, 1996 survey, shown on Umatilla County Survey record of surveys 99-121-B, "Corner was originally established in 1872 by George Williams, U.S. Deputy Surveyor, under G.L.O. Contract No. 176, as a post, from which a Tamarack 12" in diam., bears N 10°W., 65 lks (42.9') dist., A fir, 8" in diam., bears S 20°E., 20 lks (13.2') dist. Evidence Found: None. Corner Perpetuation: Set a 1½" galvanized pipe with a 2½" brass cap stamped "T6N R37E ¼ S26/S25 1996," with the following bearing trees for accessories: A Douglas fir, 27" in diam., bears N 78°18'00" W., 32' dist., marked ¼ S26 B.T., A Douglas fir, 6" in diam., Bears N56°15'00" E., 6.80' dist., marked ¼ S25 B.T., A Douglas fir, 12" in diam., bears S 57°36'00" E., 23.80' dist., marked ¼ S25 B.T., A Douglas fir 32" in diam., bears S 2°58'00" W., 23" dist., marked ¼ S26 B.T. All bearing trees tagged with nail and brass washer stamped "WA 25893 – OR 2360."

**MOUNUMENT AND ACCESSORIES FOUND:**

Found Paul Tomkins 1½" galvanized pipe with a 2½" brass cap stamped "T6N R37E ¼ S26/S25 1996," from which was also found:

- A Douglas fir, 17" in diam., bears S 66½°E., 24.00' dist.,
- A White fir, 26" in diam., bears S 2°58'N., 23.10' dist.,
- A Fir snag 9" in diam., bears N56°15'E., 6.80' dist.,
- A White fir 30" in diam., bears S 78°18'E., 32.00' dist.,
- A T-Post with tag, 8" N.

**MOUNUMENT MARKING DETAIL:**

T6N R37E  
¼  
S26 | S25  
1996  
OR 2360

**MOUNUMENT AND ACCESSORIES SET:**

No new accessories or monuments set.

**LOCATION AND COMMENTS:**

Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 848674.15  
E = 8801124.68