

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla      DATE: 01/09/2015

**CORNER DESIGNATION:** T-9, Quarter Corner for Sections 28 and 29, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 8"x16"x24" monument of stones for quarter sections 28 & 29.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found.

**MOUNUMENT MARKING DETAIL:**

T6N R37E  
S29 | S28  
1/4  
12/2014  
LS 02820

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set a 2 ½ inch Brass Cap on 1½" galvanized iron pipe, 1" above ground, marked quarter corner for sections 28 and 29, T6N,R37E by LS 02820 on 1/2014. From which:  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N46°W, 10.00 feet.  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N46°E, 12.00 feet.  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S44°W, 10.00 feet.  
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S46°E, 13.00 feet.

**LOCATION AND COMMENTS:**

Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 848023.16  
E = 8785567.04

**COMPASS DECLINATION:** 15° East


**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Joseph R. Latimer  
Corey A. West



*Greg E. Flowers*



RENEWS 12/31/15

*06/29/2015*