

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/12/08

CORNER DESIGNATION: X-25, The East One-Quarter Corner of Section 36, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

The corner was declared lost and reestablished by John Kimbrell as a 18" x 8" x 7" stone in Record of Private Surveys, Book 1, Page 492, in 1903.

MONUMENT AND ACCESSORIES FOUND: None. Falls in wheat field with no features.

MONUMENT MARKING DETAIL:

T6N  
1/4  
R36E R37E  
S36|S31  
2008  
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the Northeast Corner of Section 36 and the Southeast Corner of Section 36. At the reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 15" below ground level, (hit cemented rock, could not dig further). Cap is marked as shown in "Monument Marking Detail".

New Accessories:

- A silver deep-1 magnet bears North 19 1/2° East, 26.5 feet.
  - A purple deep-1 magnet bears South 72 1/2° East, 36.8 feet.
  - A blue deep-1 magnet bears South 12° West, 36.3 feet.
  - An orange deep-1 magnet bears North 85° West, 32.5 feet.
- Deep-1 magnets are buried 24" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in middle of wheat field, no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 842337.22  
E = 8775226.10

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36X25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*With: R. Wells*  
OREGON  
JULY 22, 19 /  
WILLIAM R. WELLS  
1106

*Expires 6-30-10*