

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/05/2015

CORNER DESIGNATION: X-13, Quarter Corner for Sections 33 and 34, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post and rock in mound of rock for quarter sections 33 & 34.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T6N
¼ S33|S34
R37E
01/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½" brass cap on 1½" galvanized iron pipe, marked quarter corner for sections 33 and 34, T6N, R37E by LS 02820 01/2015. Set 7 inches above ground with rock collar around base of pipe on steep north facing hill, from which:

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N40°W, 10.20 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N38°E, 8.00 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S12°W, 8.50 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S23°E, 10.20 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 843035.47

E = 8790864.73

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015