

MOUNUMENT AND ACCESSORIES FOUND:

Found a 2½” pipe with ¾” BLM brass cap, 0.6” above ground surface,
An 18 ins. diam., Fir with healed blaze and with existing bearing tag, bears “S. 48° E., 67.70 ft.”
A 27 ins. diam., Douglas fir bears N 23½°E., 46.30 ft., the existing bearing tag is marked “N 20½°
W. 70lks.”
A 25 ins. diam. White fir, with partially healed blaze, bears S 72½°W., 37.20 ft.
Found a cut-off and rotting 21 ins. diam., fir stump, with blaze and visible scribing, bears N. 12°
W., 70.30 ft. dist.

MOUNUMENT MARKING DETAIL:



MOUNUMENT AND ACCESSORIES SET:

Blazed, scribed and tagged a 9 ins. diam., White fir bearing, S 15° W., 55.00 feet, marked T6N
R37E S24 BT.
Blazed, scribed and tagged an 11 ins. diam., Ponderosa pine bearing, N 20° W., 42.30 feet,
marked T6N R37E S13 BT.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 856492.36
E = 8806162.22

COMPASS DECLINATION: 15° East


SURVEYORS’ SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F. Wendover
Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 5/21/2014

CORNER DESIGNATION: N-25, Corner for Sections 13 and 24, Township 6 North, Range 37E, Sections 18 and 19, Township 6 North, Range 38E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865, their note states "Set post and marked a basalt rock 12 x 12 x 9 in mound of stone in side hill facing S. for the Cor. Secs. 13, 18, 19, 24.

Surveyor Wayne O. Harris noted in his June 27, 1961 survey, shown on Umatilla County Survey, record of surveys 03-291-A (Drawing Number 61-112-C), "Set steel stake, 16" Ponderosa pine N 73°E-26.6"

Per the United States Department of the Interior Bureau of Land Management Survey and notes dated June 25, 1993, and execute3d by Richard L. Johnson, Phillip G. Griffin, Larry D. Holmes and Richard R. Shatto, Cadastral Surveyors, beginning October 13, 1987 and completed September 16, 1991 pursuant to Special instruction dated September 18, 1987 and Supplemental Special Instructions dated May 9, 1990, under Group Number 1405, Oregon, there notes state "Point for the cor. of secs. 13, 18, 19 and 24, at proportionate distance; there is no remaining evidence of the original corner. Set a stainless steel post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, and in a collar of stone, with a brass cap mkd.

T6N
R37 E R38E
S 13 | S 18
S 24 | S 19
1991

from which:

A fir, 22 ins. diam., bears N. 20° E., 70 lks. dist., mkd. T6N R38E S18 BT.

A fir, 6 ins. diam., bears S. 48° E., 102½ lks. dist., mkd. T6N R38E S19 BT.

A fir, 16 ins. diam., bears S. 74½° W., 57 lks. dist., mkd. T6N R37E S24 BT.

A fir, 21 ins. diam., bears N. 12° W., 106½ lks. dist., mkd. T6N R37E S13 BT.

Deposit a white "DEEP-1" magnetic marker at base of stainless steel post.

The corner is located on SE. slope in scattered timber and light undergrowth, 20 lks. E. of a dirt road, 20 lks. wide, bears N. 10° E. and S. 20° W.

From this point, a point reestablished as the cor. of secs. 13, 18, 19 and 24, recorded by Wayne O. Harris, Registered Land Surveyor No. 346 in 1960, in the Umatilla County Surveyor's Office bears N. 36° 56'30"W., 0.655 chs. dist., monumented with an iron rod, 1 in. square, firmly set and flush with the ground. This corner was tied to and utilized for control by C. Albert White, Cadastral Surveyor, during a dependent resurvey in T. 6 N., R. 37 E., in 1965, from which a bearing tree mkd. by Harris:

A ponderosa pine, 21 ins. diam., bears N. 78¼° E, 42 lks. dist., with scribe marks T6 R38 S1 S BT on partially healed blaze.

Surveyor Wayne O. Harris noted in his June 27, 1961 survey, shown on Umatilla County Survey, record of surveys 03-291-A (Drawing Number 61-112-C), "Set steel stake 16" P. pine N73°E-26.6"