


HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

This record has been prepared to provide current information regarding the condition of the corner monument and accessories as described in the survey records cited below. Verification of the position of the corner monument and dimensions to existing accessories, and the establishment of new corner accessories was not performed as part of this visit.

The source of the monumentation and dimensions cited in this record is a Dependent Resurvey of ...Portions of the South and East Boundary, and Subdivisional Lines of Township 6 North, Range 38 East, Willamette Meridian, conducted by the Bureau of Land Management, commenced on October 13, 1987, and completed September 16, 1991.



RECORD DESCRIPTION OF CORNER MONUMENT AND ACCESSORIES:

From the BLM Dependent Resurvey:

Point for the ¼ cor. of secs. 25 and 36, at proportionate distance, there is no remaining evidence of the original corner. Set a stainless steel post, 28 ins. long, 2 ½ ins. diam., 20 ins. in the ground, with brass cap mkd. (See diagram below), from which:

A fir, 16 ins. diam., bears S63 1/2°E 26 ½ lks. dist., mkd. ¼ S36 BT,

A fir 27 ins. diam., bears N 52 1/4°W 44 ½ lks. dist., mkd. ¼ S25 BT,

Deposit a white "DEEP-1" magnetic marker at base of stainless steel post. The corner is located on SW slope, 65 lks. S. of Spur, slopes S60°W, and 30 lks. N. of ravine, drains S60°W.


DESCRIPTION OF MONUMENT AND ACCESSORIES FOUND AT THIS CORNER LOCATION:

Found:

A 3" dia. Brass cap, marked as shown, on a 2 ½" stainless steel pipe, firmly set, extending 4" above ground and in a small mound of stone in the bottom of a shallow ravine, from which:

A 20" Fir, alive and in good condition with well healed single blaze (BLM 1991 SE bearing tree),

A 30" Fir, alive and in good condition with well healed single blaze (BLM 1991 NW bearing tree).



Reviews 12/31/06

I hereby certify that the above corner position was visited and found as described on October 20, 2005.

Witnesses: Tim Johnson, Gary Langlitz, Jeremy Jones

RECEIVED BY
Umatilla County Surveyor
Date 1-06
Rec'd by KK
No. 06-10-R