

V-01


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.

Surveyor General Record States:

Set post for cor. to sect's 25-30-31-36. From which:

- A 27" Fir bears N 61-30 W, 32 lks.
- A 20" Pine bears S 29 E, 29 lks.
- A 30" Pine bears S 34 W, 30 lks.
- A 10" Fir bears N 31 E, 59 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original BTs as follows:

- A 42" Fir, good condition, bears N61W, 21.1 ft., blaze healed.
- A 24" Fir, good condition, bears N31E, 38.9 ft., blaze healed.

No evidence of other BTs.

Description of monument and accessories established to perpetuate the original location of this corner

At corner position, I set 2 1/2"x30" iron pipe with brass cap marked as shown, 22" in ground, raised mound of stone 7 ft. at base to top of cap, from which:


New BTs

- A 16" Fir bears S39E, 37.7 ft. marked T6S R30E S31 BT.
- A 8" Fir bears S44W, 83.1 ft. marked T6S R30E S36 BT.

Nailed brass washer to BT blaze.  
 Set steel fence posts 5+ ft. North and 5+ ft. West of corner.  
 Used steel tape and magnetic compass with 20° E declination.  
 Measured to face of blaze on original BTs and center of new BTs.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Duane J. Griffith*  
 OREGON  
 JULY 10, 1934  
 DUANE J. GRIFFITH  
 644



Office of Surveyor County of Wasatch  
 State of Oregon, I hereby certify that the within Instrument was filed in this office  
 for record on the 13 day of April, 1974, at        o'clock        m., (signed)  
*Ralph Thompson* by         
 (COUNTY OFFICIAL) (DEPUTY)

V-1

S-58-M