

USDA-FOREST SERVICE

Index

File No. A-17

T6S

R30E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSN 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

T5SR30E

S33

S3

S2

T6S1R30E

CC

1976

OPLS 598

1

1 Describe corner monument found

1 Steel pipe extending 4" above the ground with a 2 1/2" brass cap stamped as shown in the diagram. Monument is in a stone mound.

1

1

1

1

x

Photo Identification Data

Photo No. 1197-210

filed at Pendleton, OR

Object Ident. bearing trees

Ident. by D. Haddock

Signature

1

1 Describe bearing trees or other official accessories found
 1 The remains of a 21" Ponderosa Pine bears S50°W, 29.7'. The tree is broken off about 8' in the air. A 20" Ponderosa Pine bears S49°E, 108.9' with visible scribing.

1

1

1

x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1

1 Describe corner location relative to near-by features, also how to reach corner
 1 From the junction of roads 5312 and 5320, follow 5320 east 1.6 miles to road 5320110. Then follow road 5320 south 0.4 miles to a east-west fence. Follow this fence east approximately 1000' past the SE corner of section 33 to the corner which is approximately 50' south of the fence line.

1

x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Haddock

Land Surveyor

Pendleton, OR

June 1988

CORNER RECORD (PERPETUATION)

X-----X
 Monument: Describe new monument set, or work done to preserve existing monument
 Set 30" aluminum pipe 22" in the ground at the intersection of the First Standard Parallel and the section line from the south. Stamped the 2 1/2" aluminum cap as shown to the right. Made a stone collar around the monument. The new monument is about 56' north of the amended monument set by DPLS 598. Set a steel fence post 5' east of the monument and attached Forest Service Land Survey Monument and Property Boundary signs. Stamped the brass cap set by DPLS 598 "AM".

T5SR30E	
S34	
S3	S2
T6S	R30E
CC	
1988	
PLS 852	

x-----x
 Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Used one old bearing tree as a bearing tree for the new monument. This tree is a 14" White Fir which bears S21°30'W, 78.7'. Established one new bearing tree for the new monument. This tree is a 15" Ponderosa Pine which bears S46°15', 35.8'. Scribed this tree T6S R30E S2 CC BT in a 30" blaze. Attached an aluminum washer stamped RLS 852 between the letters B and T on the new tree. Painted all the bearing trees with a red band. Attached Forest Service Land Survey Monument and Bearing Tree signs to each of the trees.

x-----x

Work done by	David L. Haddock	Title	Land Surveyor	Date	Nov 1988	State Registration No.	
Certified cor. record prepared?	yes x		no	Filed at	Pendleton, OR	or Agency	852
						Date	Dec 1988 Jan 1989

x-----x

REMARKS

x-----x

Index File No.	A-17	T.6S.	R.30E.	M. Willamette	Tract or Survey No	Cor.
----------------	------	-------	--------	---------------	--------------------	------

USDA-FOREST SERVICE

Index File No. A-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. CC


T 6S R. 30E

R.D. UKIAH County UMATILLA

Merid. WILLAHETTE

N.F. UMATILLA State OR.

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 20" PINE BRS S49°E 108² FT WITH SCRIBING VISIBLE
 A 21" PINE " S50°W 292 " MKD S 3 CC BT
 A STUMP HOLE BRS. NORTH 132 FT.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

COR IS 50 FT. SOUTH OF E-W FENCE

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Signature
R. O. BENT

Title
LANDSURVEYOR

Division _____ *Headquarters* _____

Date
9-30-76

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET 2 1/2" x 30" IRON PIPE W/ BRASS CAP MKD

T5SR30E	
533	
S3	S2
T6S	R30E
CC	
1976	
OPL5598	

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

BOTH ORIG. BTA OK
I PAINTED A RED BAND AROUND BTA & TAGGED BOTH WITH BT TAGS

Work Done By: R.D. Baggett Title: LAND SURVEYOR Date: 9-30-76 State Registration No. or Agency: OPL5598

Certified Cor. Record Prepared? Yes No Filed At: UMATILLA C.S. Date: _____

REMARKS

Index File No. A-17 T. R. M. Tract or Surv. No. Cor. 12 13