

USDA-FOREST SERVICE

Index

File No. A-18

T68

R30E

Merid. Willamette

R.D.

R.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

W1/16

CC 152

1977

PLS 933

1

1 Describe corner monument found

1

1 Steel pipe extending 22" above the ground with a 2 1/2" brass cap stamped as shown in the diagram, in a mound of stone.

1

1

1

x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

1

1 Describe bearing trees or other official accessories found

1

1 A 18" White Fir bears S35°56'W, 90.6' with healed scribe.

1

1 A 11" White Fir bears S59°14'E, 13.4' with healed scribe.

1

1

x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1

1 Describe corner location relative to near-by features, also how to reach corner

1

1 From the junction of roads 5312 and 5320, follow 5320 east 1.6 miles to road

1

1 5320110. Then follow road 5320110 east 0.6 miles to road 5320130. Follow road

1

1 road 5320130 south 0.4 miles to an east-west fence. Follow the fence west

1

1 approximately 500' to the corner.

1

x

Signature

*David L. Hadlock*

Title

Land Surveyor

Division

Headquarters

Pendleton, OR

Date

June 1988

7100.52

CORNER RECORD (PERPETUATION)

X \_\_\_\_\_ X  
 Monument: Describe new monument set, or work done to preserve existing monument

TRUE CORNER POINT

Set steel guard post 5' west of the ~~monument~~ and attached Forest Service Land Survey Monument and Property Boundary signs.

X \_\_\_\_\_ X  
 Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Repainted bands and blazes on trees Red. Attached Forest Service Land Survey Monument signs to trees.

X \_\_\_\_\_ X

|                                 |                  |       |               |          |          |                        |     |
|---------------------------------|------------------|-------|---------------|----------|----------|------------------------|-----|
| Work done by                    | David L. Haddock | Title | Land Surveyor | Date     | Nov 1988 | State Registration No. |     |
| Certified cor. record prepared? | yes              |       | no x          | Filed at |          | or Agency              | 852 |
|                                 |                  |       |               |          |          | Date                   |     |

X \_\_\_\_\_ X  
 REMARKS

X \_\_\_\_\_ X

|                |      |       |        |               |                    |      |
|----------------|------|-------|--------|---------------|--------------------|------|
| Index File No. | A-1B | T.6S. | R.30E. | N. Willamette | Tract or Survey No | Cor. |
|----------------|------|-------|--------|---------------|--------------------|------|

USDA-FOREST SERVICE

Index File No. A-18

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_

T 6S. R. 30E.

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T. 5S., R. 30E.

W. 1/16

CC S.2

T. 6S., R. 30E.

DESCRIBE CORNER MONUMENT FOUND

None  
*Set brass cap*

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the intersection of U.S. Forest Roads 419N and 537N, go East by South to fence 2.1 miles, then walk along fence East 40 chns. to corner.

Signature  
*David H. Kumbler*

Title

Division

Headquarters

Date

*OPLS*

*933*

*7-77*

7100-52-(3/68)

## CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½" x 30" iron pipe with brass cap.  
 Pipe is 8" in ground.  
 Mound of stones to cap.

Stamped:

T. 6S., R. 30E.  
 W. 1/16

CC S.2

1977  
 PLS 933

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 18" fir bears S. 35°56' N. 90.6 ft.  
 A 11" fir bears S. 59°14' E. 13.4 ft.

Set a steel fence post 3 ft. West of corner w/sign.  
 Painted red band around BT trees w/sign.

10

Work Done By. T. Hamby Title Party Chief Date 6/23/77 State Registration No. \_\_\_\_\_  
 or Agency \_\_\_\_\_

Certified Cor. Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_ 11

REMARKS

12

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

13