

USDA-FOREST SERVICE

Index

File No. A-24

T6S

R30E

Merid. Willamette

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

1977

R.D.

1 Describe corner monument found

N.F.

1 Steel pipe extending 4" above the ground with a 2 1/2" brass cap stamped as shown in the diagram.

E1/16

S1

T6S R30E

PLS 933

x

Photo Identification Data

1

1 Describe bearing trees or other official accessories found

Photo No.

1 A 14" White Fir bears N76°47'E, 18.6' with healed scribe.

filed at

1 A 9" Lodgepole Pine bears S7°33'W, 19.5' scribed E1/16 S1 BT and is dead and down.

Object Ident.

1

Ident. by

1

Signature

1

x

Plane Coordinate Position Data

1

1 Describe corner location relative to near-by features, also how to reach corner

State

Zone

1 From the junction of roads 5312 and 5320, follow 5320 east 1.6 miles to road-

X

1 5320110. Then follow road 5320110 east 1.9 miles to the end of the improved rock

Y

1 road. From the end of this road, walk down the hill east along the posted line

Estab. by

1 approximately 1500' to the corner.

Agency

1

x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Haddock

Land Surveyor

Pendleton, OR

June 1988

CORNER RECORD (PERPETUATION)

X-----X  
 Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

X-----X  
 Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Established a new bearing tree. This 9" Lodgepole Pine bears S40°30'E, 34.9' from the corner. Scribed this tree E1/16 S1 BT on a 24" blaze. Nailed an aluminum washer stamped RLS 852 between the letters B and T. Made bands around all three trees and painted the bands and the scribes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to each tree.

X-----X  
 Work done by David L. Haddock Title Land Surveyor Date Nov 1988 State Registration No. 852  
 Certified cor. record prepared? yes x no Filed at Pendleton, OR Date JAN Dec. 1988 1989

X-----X  
 REMARKS

X-----X  
 Index File No. A-24 T.6S. R.30E. M. Willamette Tract or Survey No. Cor.

USDA-FOREST SERVICE

Index File No. A-24

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_

T 6S. R. 30E.

R.D. Ukiah County \_\_\_\_\_

Umatilla \_\_\_\_\_

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T. 5S., R. 30E.

E. 1/16 CC

T. 6S., R. 30E.

S.1

DESCRIBE CORNER MONUMENT FOUND

None

*Set brass cap*

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the intersection of U.S. Forest Road 419N and 537N, go East 1.8 miles to Gulliford crossing, then East 2.2 miles to fence, then along fence about 20 chns. to corner.

Signature

*David H. Kuler*

Title

*OPLS*

Division

Headquarters

*933*

Date

*7-77*

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" x 30" iron pipe with brass cap.  
Pipe is 22" in ground.  
Mound of stone to cap.  
Stamped:

E 1/16 CC

S.1  
T. 6S., R. 30E.  
1977  
PLS 933

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 12" pine bears N. 76°47' W. 18.6 ft.  
A 9" pine bears S. 07°33' W. 19.5 ft.  
Set steel fence post 3 ft. East of corner w/sign.  
Painted red band around BT trees w/sign.

10

Work Done By T. Hamby Title Party Chief Date 6/23/77 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_

Certified Cor. Record Prepared? Yes  No \_\_\_\_\_ Filed At: \_\_\_\_\_ Date \_\_\_\_\_ 11

REMARKS

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13