

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Frank W. Campbell, under Contract No. 380.

Surveyor General Record States:

79.80 intersect 1st std. parallel 9.30 chs. East of cor. to secs. 31 and 32 at which point I set a pine post for c.c. from which:

- A pine 12 in. in diam. brs. N. 12° W. 71 lks. dist.
A pine 48 in. in diam. brs. S. 41° E. 59 lks. dist.
A pine 18 in. in diam. brs. S. 30° W. 79 lks. dist.

No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original corner post. I establish this corner at record bearing and distance from 2 original bearing trees as follows: From the corner point:


- A 31" pine stump bears N. 12° W. 46.9 ft. mkd. "B" in blaze that I opened. Blaze is 9 inches from center of tree. The remains of a dead and down 28" pine blowdown bears S. 41° E. 38.9 ft. I found one axe mark about where the scribing blaze would have been, the blaze and scribing are completely weathered out.
A 34" pine bears S. 47° W. 59.5 ft. mkd. R.30E. T6S. on old fire scar. This tree is leaning badly.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" iron pipe 30" in the ground with brass cap marked as shown. From which I scribe NEW BEARING TREES:

- A 10" fir bears S. 32° E. 21.3 ft. mkd. T6S R30E S4 CC BT.
A 20" fir bears S. 21° W. 31.2 ft. mkd. T6S R30E S5 CC BT.

I nailed a brass washer marked "OPLS 598" to BT blaze of both trees. Set a steel fence post 5' West of corner. Corner is 8 ft. North of E-W fence line. Used compass with 20° E. variation and steel tape, measuring to the center of the new BTs.




REGISTERED PROFESSIONAL LAND SURVEYOR

Robert D. Bagett (handwritten signature)

OREGON JULY 12, 1963 ROBERT D. BAGETT 598

Sept. 30, 1976



Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
(COUNTY OFFICIAL) by (DEPUTY)

A-9
S-60-M