


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-2

History of original corner establishment:
None



Description of corner evidence found:
None

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:
From which

T6S R30E
W 1/16
C-----C
 S6
1979
PLS 346

White Fir, 7" Dia., BRS. N32°W., 12.2 Ft. Dist.
Marked: CW 1/16 S6 BT

White Fir, 7" Dia., BRS. S10°W., 14.4 Ft. Dist.
Marked: CW 1/16 S6 BT

6' iron fence post with "Survey Monument" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped:
PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the day of

..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

ORIGON
MAY 6, 1955
WAYNE O. HARRIS
346

RECEIVED BY

Form R6-7100-57 (9/71) Umatilla County Surveyor
Date 10-17-79
Rec'd By mdj
No. Q-1171-B

C-2