


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881
by Frank W. Campbell, under Contract No. 380

Surveyor General Record States:

80.00 set a pine post for corner to secs. 2, 3, 10, 11
from which:

- A pine 8 in. in diam. brs. S. 37° E. 21 lks. dist.
- A pine 15 in. in diam. brs. S. 74° W. 64 lks. dist.
- A pine 40 in. in diam. brs. N. 22° W. 100 lks. dist.
- A pine 8 in. in diam. brs. N. 39° E. 29 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original corner post. I establish corner point at record bearing and distance from one remaining BT stump from the corner point:

The remains of a 33" pine stump brs. N. 22° W. 66.0 ft. dist. mkd S.
No evidence found of the other BTs.

I found a 3"x3"x4' post mkd with the section numbers on all four sides laying at the position I established for the corner. I don't believe this post to be the original as it has been marked with a knife instead of a scribe and is not weathered enough.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point: Set a 2½"x30" iron pipe 26" in the ground marked as shown:
From which I scribe NEW BEARING TREES:

- A 17" Fir bears N. 27° E. 71.4 ft. mkd. T6S R30 E S2 BT.
- A 12" Fir bears S. 48° E. 28.7 ft. mkd. T6S R30 E S11 BT.
- An 8" Fir bears S. 35° W. 19.0 ft. mkd. T6S R30 E S10 BT.
- A 9" Fir bears N. 47° W. 24.0 ft. mkd. T6S R30 E S3 BT.

I nailed a brass washer mkd "OPLS 598" to the BT blaze of the new BTs. Set a steel fence post 5 ft. West of corner. Surrounded pipe with a mound of stone. Corner is 100 ft. East of old road. Used compass with 20° East variation and a steel tape, measuring to face of blaze of old BT and to center of new BTs.


REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept. 30, 1976

County Surveyor Umatilla
Office of County of
State of Oregon
I hereby certify that the within instrument was filed in this office
for record on the day of 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)



E-17