


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Frank W. Campbell, under Contract No. 380.

Surveyor General Record States:

80.00 set a pine post for cor. to secs. 1, 2, 11, 12 from which:

- A pine 20 in. in diam. brs. S. 54° W. 75 lks. dist.
- A pine 40 in. in diam. brs. N. 66° W. 70 lks. dist.
- A pine 20 in. in diam. brs. N. 71° E. 72 lks. dist.
- A pine 20 in. in diam. brs. S. 11° E. 111 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found remains of the original charred corner stake from which THE ORIGINAL BEARING TREES:

- A 30" pine stump bears S. 52° W. 49.5 ft. mkd. BT.
- A 38" pine stump bears N. 70° W. 46.2 ft. mkd. BT.
- A 12" pine stump bears S. 13° E. 75.0 ft. no mks remain.
- No remains of BT in sec. 1.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point: Set a 2½"x30" galvanized iron pipe 25" in the ground with a brass cap marked as shown. From which I scribe NEW BEARING TREES:

- A 7" fir bears N. 28° E. 17.0 ft. mkd. T6S R30E S1 BT.
- A 15" pine bears S. 77° E. 59.3 ft. mkd. T6S R30E S12 BT.
- A 9" pine bears S. 16° W. 67.5 ft. mkd. T6S R30E S11 BT.
- A 14" pine bears N. 45° W. 15.6 ft. mkd. T6S R30E S2 BT.


I nailed a brass washer marked "OPLS 598" to the BT blaze of these trees. Set a steel fence post 5 ft. West of corner. Surrounded pipe with a mound of stone. Corner is 10 ft. North of Snake Creek. Used compass with 20° E. Variation and steel tape measuring to center of new BTs.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept. 30, 1976



Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

E-21