


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Frank W. Campbell, under Contract No. 380

Surveyor General Record States:

Set a basalt stone 10x8x8 in a md. of stone for 1/4 sec.

Pine 24 in. in diam. brs. S 18° E. 60 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original 1/4 corner stone. I establish this corner at record bearing and distance from the original bearing tree. From the corner point:

A 24" pine stump bears S. 18° E. 39.6 ft. mkd. BT at the base the scribing blaze axe marks are visible at the top of the stump.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" galvanized iron pipe 20" in the ground with brass cap marked as shown. From which I scribe NEW BEARING TREES:

A 12" pine bears N. 49° E. 55.5 ft. mkd. T6S R30E 1/4 S1 BT.

A 9" pine bears S. 34° E. 25.5 ft. mkd. T6S R30E 1/4 S12 BT.


I nailed a brass washed marked "OPLS 598" to BT blaze of both trees. Set a steel fence post 5 ft. west of corner. Raised a mound of stone 3 ft. base to top of pipe. Corner is 10 ft. SE of old logging road. Used compass with 20° East variation and steel tape measuring to center of new BTs.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. Bagett*

OREGON  
JULY 12, 1963  
ROBERT D. BAGETT  
598

*Sept. 30, 1976*



Office of.....County Surveyor..... County of.....**Umatilla**  
 State of.....**Oregon**....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

*E-23*

*S-60-M*