


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.

Surveyor General Record States:

Set post for  $\frac{1}{4}$  cor. From which:

- A 8" Pine bears N 41 E, 19 lks.
- A 8" Pine bears S 68 W, 26 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:  
Found NE BT as follows:

A 18" Tamarack, dead, bears N41E, 12.5 ft., scribes visible.


Description of monument and accessories established to perpetuate the original location of this corner

At corner point, from original BT, I set 2 $\frac{1}{2}$ "x30" iron pipe, with brass cap marked as shown 28" in ground, from which:

New BTs

- A 13" Fir bears S83E, 23.3 ft. marked  $\frac{1}{4}$ S7 T6S R30E BT.
- A 10" Fir bears S30W, 6.6 ft. marked  $\frac{1}{4}$ S12T6S R29E BT.

Nailed brass washer to BT blaze.  
Set steel fence post 5+ ft. South and 5+ ft. West of corner.  
Used steel tape and magnetic compass with 20° E declination.  
Measured to face of blaze on original BT and center of new BTs.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 13 day of Aug, 1974 at        o'clock        m., (signed)  
Ralph Thompson by         
 (COUNTY OFFICIAL) (DEPUTY)

G-1