


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A BASALT STONE 20"x12"x3" IN A MOUND OF STONES

Description of corner evidence found:

NONE

Description of monument and accessories I established to perpetuate the ~~original~~ location of this corner:

BY SINGLE PROPORTIONING THE DISTANCE BETWEEN THE QUARTER CORNERS NORTH AND SOUTH OF THIS SECTION CORNER I SET:


A 3"x30" IRON PIPE WITH A BRASS-CAP MARKED:

T6S	
R30E	R31E
S12	S7
S13	S18
1978	
PLS 346	

FROM WHICH: 24" PINE S76W 137.4' MARKED T6S R30E S13 BT  
 22" PINE N51W 101.1' MARKED T6S R30E S12 BT  
 24" PINE N77E 73.8' MARKED T6S R31E S7 BT  
 22" PINE S29E 70.1' MARKED T6S R31E S18 BT

ALL BT'S HAVE A BEARING TREE TAG, ATTENTION SIGN, A RED PAINTED STRIPE, AND A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE.

SURVEY IS RECORDED ON USFS CONTRACT #40-04R3-8-0999 AND UMATILLA COUNTY SURVEY # P-96.



Office of...COUNTY...SURVEYOR..... County of...UMATILLA.....  
 State of...OREGON..... I hereby certify that the within instrument was filed in this office  
 for record on the... day of...OCTOBER....., 19...78  
*Wayne O. Harris* by .....  
 (COUNTY OFFICIAL) (DEPUTY)

J-25