


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A PINE POST

7" PINE S22E 49 LKS.  
7" PINE S08W 51 LKS.

Description of corner evidence found:

16" PINE S22E 32.3' SCRIBING NOT OPENED UP

Description of monument and accessories established to perpetuate the original location of this corner:

A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED:

T6S  
R30E R31E  
¼  
S13 S18  
1978  
PLS 346

14" FIR S36W 7.5' MARKED: ¼ S13 BT

BOTH BT'S HAVE A RED-PAINTED STRIPE, BEARING TREE TAGS, AND AN ATTENTION SIGN. THE NEW BT HAS A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE. THERE IS A STEEL FENCE POST ON LINE NEAR THE CORNER.



Office of...COUNTY...SURVEYOR..... County of.....UMATILLA.....  
 State of.....OREGON....., I hereby certify that the within instrument was filed in this office  
 for..... on the..... day of....., 19.....  
*Wayne O. Harris* (COUNTY OFFICIAL) by..... (DEPUTY)

RECEIVED SEP 11 1978

L-25