


n-00
R-01

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by Meldrum and Campbell under General Land Office Contract No. 380. Surveyor General Records states: Set a basalt stone 22" X 20" X 6" in mound of stone for cor. to sections 19, 24, 25, 30.



No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

None


(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At proportionate distance I set 2 1/2" X 30" iron pipe with brass cap marked as shown 14" in ground from which:

- A 24" Juniper bears N 27° E, 124.8 ft. marked T6S R30E S19 BT.
- A 11" Pine bears S 14° E, 106.4 ft. marked T6S R30E S30 BT.
- A 12" Juniper bears S 76° W, 73.3 ft. marked T6S R29E S25 BT.
- A 13" Juniper bears N 45° W, 94.7 ft. marked T6S R29E S24 BT.

Raised mound of stone 5 ft. base to top of cap. Set steel fence post 5+ ft. South.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane J. Griffith

OREGON
JULY 10, 1954
DUANE J. GRIFFITH
644

Brass Washer nailed to BT blazes. Used steel tape and magnetic compass with 19° 30' East declination. Measured to center of all BTs.

Office of..... County of.....

State of....., I hereby certify that the within Instrument was filed in this office for record on the day of

..... by
(COUNTY OFFICIAL) (DEPUTY)

R-1

S-58-M