



CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-1 4-25

History of original corner establishment: Corner originally established by Rufus S. Moore in 1881: At the intersect point on the standard parallel, 411 links east of the standard section corner for sections 35 and 36, Range 31 East, set a basalt stone 24"x12"x6", and dug pits for closing corner from which a 4" pine bears N42°E, 190 links (125.4 ft.).



In 1968, the B.L.M. established the true point of intersection by survey and set an iron post 28" long, 2½" in diameter, 20" in the ground in a mound of stone, with a brass cap marked: The original corner stone was found N0°06'W, 0.06 chains (3.96 ft.) of the true corner point from which the original B.T., a 37" ponderosa pine, bears S42°E, 190 links. From the brass cap monument: A 10" ponderosa pine bears S89°E, 292 links (192.72 ft.), scribed "T6S R32E S6 CC BT", a 20" ponderosa pine bears S20°W, 185 links (122.1 ft.) scribed "T6S R31E S1 CC BT". Original stone is buried in place.



Description of corner evidence found:

At the corner point, I found the brass capped iron pipe monument as described above and the original corner stone, marked "CC", is in a hole 4.0 feet to the north. I occupy the corner point with a theodolite and determine true azimuth by reference to the bearing trees established by the B.L.M.

Accessories found:

- A 12" ponderosa pine is 91° azimuth, 192.5 ft., scribes visible on a nearly healed blaze.
- A 22" ponderosa pine is 200° azimuth, 121.6 ft., scribes visible on a nearly healed blaze.
- A 37" ponderosa pine snag is 135° azimuth, 132.4 ft., scribes visible on a charred blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

This corner is in danger of being destroyed by future road construction, I, therefore, reference the true corner point as follows:

I place a 4"x5" metal target on a 28" ponderosa pine which is 76° 08.8' azimuth, 269.9 feet distant, and a 5/8"x24" iron rod in a mound of stones on the same azimuth at 164.85 feet distant; a 4"x5" metal target on a 30" lone ponderosa pine which is 341° 19.3' azimuth, 232.2 feet distant, and a 5/8"x24" iron rod in a mound of stones on the same azimuth at 137.26 feet distant; an iron rod with a plastic cap affixed and marked "FHWA CP" and identified with a 48" lath marked "RP-P 276+37 41" and two 18" stakes similarly marked, is 84° 34.3' azimuth, 125.68 feet distant.

I hereby certify the above corner point was referenced as hereon described on May 12, 1983.

Witness: Susan E. McGranahan

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 26 day of MAY, 1983
David H. Klein by.....
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 date 6-83
 rec'd by [Signature]
 No. 83-134-R