


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 5

History of original corner establishment:

This corner was originally established by Rufus S. Moore on July 4, 1881 under his GLO contract number 382, as follows:

Set a basalt stone 24" x 12" x 8" and dug pits for the corner to sections 17, 18, 19 and 20.



Description of corner evidence found:

Found a basalt stone, 23" x 14" x 9" tipped to the west. The stone is marked with 3 grooves on the south face and one groove on the west face.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 2 1/2" x 30" aluminum pipe 26" into the ground in a mound of stones. A 3 1/4" aluminum cap attached is marked as shown in the diagram above. I bury the corner stone along the northwest side of the pipe, from which:

- A 22" Ponderosa Pine bears S62°W, 90.4 feet scribed "T6S R31E S19 BT".
- A 25" Ponderosa Pine bears N67°30'E, 144.4 feet scribed "T6S R31E S17 BT".
- A 19" Ponderosa Pine bears S19°30'E, 139.1 feet scribed "T6S R31E S20 BT".
- A 24" Ponderosa Pine bears N32°45'W, 79.8 feet scribed "T6S R31E S18 BT".

The bearing trees have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze and have sign 54-3, Bearing Tree, nailed above the blazes and sign 54-9, Land Survey Monument, nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on June 15, 1994. Magnetic declination: 20° E.

NAD1983 Geographic Position (+ or - 2 to 5 meters).
Latitude 45-02-22.84 N
Longitude 119-01-22.16 W

Witnesses: Rachelle Fletcher
Dustin Olson

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Office of COUNTY SURVEYOR County of UMATILLA State of OREGON
I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____

(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor
Date 6-94
Rec'd By KK
No. 94-67-R

☆ GPO-798-276