


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-21

History of original corner establishment:

ESTABLISHED IN 1884 BY FRANK @. CAMPBELL:

Set a basalt stone 18 inches by 15 inches by 8 inches, 12 inches in the ground for closing corner for Sections 1 and 2 marked.
"CC"



With 1 notch on the east and 5 notches on west edges from which:

- A 20" tamarack bears S. 31°E., 27 links (17.8 ft.) marked T.6S., R.32E., S.1 BT
- A 10" pine bears S. 78°W., 141 links (93.1 ft.) marked T.6S., R.32E., S.2 BT

Description of corner evidence found:

An 18" pine bears S. 78°W., 141 links (93.1 ft.) with scribe marks visible on partially healed blaze.


A stump hole with an 18" larch lying alongside bears S. 31°E., 27 links (17.8 ft.). Scribes, "CC", are plainly visible on the larch.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined from the original bearing trees: Set a 2½" iron post, 30" long, 20" into the ground in a mound of stones, with a 3" brass cap marked:

From which:

- A 10" pine bears S. 59°E., 16½ links (10.9 ft.) scribed T.6S., R.32E., S.1 CC BT.
- A 9" fir bears S. 73°W., 34 links (22.4 ft.) scribed T.6S., R.32E., S.2 CC BT.



I hereby certify the above corner was perpetuated as hereon described in July 1982. Witness: Scott McMullin

Office of COUNTY SURVEYOR County of UMATILLA
 State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 11 day of August, 1982.
David H. Klein by _____
 (COUNTY OFFICIAL) (DEPUTY)

A-21

RECEIVED BY
 Umatilla County Surveyor
 Date 8-82
 Rec'd By BLS
 No. 82-101-R