

USDA-FOREST SERVICE

Index

File No. A-21

T 6S R. 32

Merid. Will.

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. \_\_\_\_\_  
Cor. C | C  
No. \_\_\_\_\_

S2 | S1  
C | C

**CORNER DIAGRAM**



T5S  
S35  
-----  
S2 | S1  
C | C  
T6S R32E  
LS 1106  
1986

**DESCRIBE CORNER MONUMENT FOUND**

A 2½" by 30" galv. iron pipe with flaired flange and 2½" brass cap, by LS 1636, protruding 8" from a mound of stone in a rut in an existing road.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

A 25" pon. pine bears S60°E-46.76 feet to a nail set in the west side of tree with vis. scribing on a partly healed blaze. (1982 bearing tree). A 19" pon. pine bears S79½°W-93.1' with scribing vis. on a partly healed blaze. (Orig. bearing tree). A 12" doug. fir bears S73°W-22.4' with healed blaze. (1982 bear. tree). A 18" down western larch snag bears S31°E-17.8' to

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

root hole and stump remains with scribing visible under tree. (Original bearing tree).

The corner is located in the north rut of an old road north of "P" line station 29+00. Walk to corner from road closure sign at the junction of road 52-200.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

Signature  
*Willie R. Wells*

Title  
PLS

Division

Headquarters

Date  
4-7-86

FS-7100-52 (3/68)

2

3

4

5

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

This corner is likely to be destroyed by a new timber sale road. I set a 5/8" by 20" iron rod with 1 1/2" aluminum cap marked as shown in diagram, to bedrock. The top of the aluminum cap is 6" below the rut in the road at the corner point. Buried monument by LS 1636 horizontally next to the new monument. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree.

9

**ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS, ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A reference monument bears S13 1/2° E-145.18', marked RM NW S1 145.18 FT LS 1106 1986. An arrow points toward the corner point. V  
cc  
 A reference monument bears S78 1/2° W-132.26' marked RM NE S2' CC 132.26 FT LS 1106 1986. An arrow points toward the corner point. The angle between the two reference monuments, as observed from the corner point is 92° 13', measured with a theodolite. Reference monuments are 5/8" by 30" iron pins with 1 1/2" aluminum caps. A 6' steel fence post with sign 54-9 attached is set within one foot of each reference monument.

10

Work Done By W.R. Wells Title PLS Date 4-7-86 State Registration No. or Agency 1106

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla Co. Surveyor's Of Date           

11

**REMARKS**

Index A File No. 21 T. 6S R. 32E M. Will. Tract or Surv. No.           

Cor. S2 | S1  
-C | Q

12

13