

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-24


History of original corner establishment:

U.S. Cadastral Surveyors, under special instructions Group Numbers 350 and 643, set a 2 1/2" X 30" iron post with a brass cap marked:

monument 24" in the ground, from which:

- A Fir, 18" dia., N21°E, 36 lks.
- A Pine, 10" dia., S42°W, 113 lks.

El/16  $\frac{S24}{S25}$   
1968



Description of corner evidence found:

I found a 2 1/2" iron pipe with a brass cap marked: in a mound of stone. From the corner:

El/16  $\frac{S24}{S25}$   
1968

- A White Fir, 25" dia., N21°E, 23.8 ft., with a healed blaze.
- A Ponderosa Pine, 13" dia., S47 1/2°W, 74.1 ft., with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

I painted the blazes of the BTs and a 6" band around them red and attached new BT tags and "Land Survey Monument" signs. I drove a 6' steel fence post within 5' of the corner and attached a "Land Survey Monument" sign.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20 1/2°E.

Oct. 31, 1986

REGISTERED PROFESSIONAL LAND SURVEYOR

*Fayette S. Munro*

OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 12-11-86

Rec'd By A

No. 86-138-M

GPO-798-278