

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

The original corner was established by Frank W. Campbell on June 3, 1883, under GLO contract No. 468, as follows: Set a post for the corner from which: A 24" fir bears S58°E, 19 links (12.54 feet). A 12" fir bears N40°W, 12 links (7.92 feet). In 1967, the BLM, under Groups No. 350 and 643, found a mound of stones at the corner from which a decayed fir stump with visible scribes bears S58°E, 19 links (12.54 feet). A 20" fir with healed blazes bears N40°W, 12 links (7.92 feet). The BLM set a 2 1/2" iron post with a brass cap attached marked as shown in the diagram, from which: A 19" pine bears S3°E, 22 1/2 links (14.85 feet). A 9" fir bears N83°30'W, 23 1/2 links (15.51 feet). A 7" fir bears N77°E, 21 1/2 links (14.19 feet). Fayette S. Munro, PLS 1832, on October 30, 1986, found the corner to be as described by the BLM and in satisfactory condition, and the following bearing trees: A decayed stump with scribes visible bears S58°E, 12.5 feet. A 21" Douglas-fir with a healed blaze bears N40°W, 7.9 feet. A 21" Ponderosa Pine with visible scribes bears S3°E, 14.8 feet. A 11" White Fir with a healed blaze bears N80°W, 15.5 feet. A 9" White Fir with a healed blaze bears N77°E, 14.2 feet. On July 17, 1987, Duane I Griffith, PLS 644, found the corner as described by the BLM, except as follows: The 21" fir N40°W, 7.9 feet is nearly dead. The 9" fir N77°E, 14.2 feet is nearly dead. The 11" fir N83°30'W, 15.5 feet is nearly dead. Griffith established a new bearing tree: A 27" Ponderosa Pine bears S40°W, 72.67 feet.

DIAGRAM:

1/4
S25 S30
R32E R33E
T6S
1967

DESCRIPTION OF CORNER EVIDENCE FOUND:

A 2 1/2" iron pipe with a 3 1/4" brass cap attached which is marked with the BLM logo and as shown in the diagram above. The cap is protruding 4" above the ground and is surrounded by a mound of stones, from which: A burnt out root hole, all that remains of the original bearing tree to the southeast, bears S58°E, 12.5 feet. A 21" fir snag with a healed blaze bears N37°W, 8.3 feet. A 29" Ponderosa Pine with charred scribes visible on double blazes bears S44°W, 73.0 feet. A 22" Ponderosa Pine with charred scribes visible on a partly healed blaze bears S0°45'W, 15.3 feet. A 12" fir snag with a healed blaze bears N80°W, 15.4 feet. A 9" fir snag with a healed blaze bears N79°E, 14.1 feet.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

New references:

A 30" Ponderosa Pine scribed "1/4 S30 BT" on double blazes bears N65°E, 90.5 feet.
 A 10" Ponderosa Pine scribed "1/4 S25 BT" on double blazes bears N11°45'W, 114.0 feet.
 A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636", attached at ground level, bears N71°W, 80.0 feet.

The new bearing trees have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze, a 54-3, "Bearing Tree", sign nailed above the blazes and a 54-4, "Attention", sign nailed to the back.

I hereby certify the above corner was perpetuated as hereon described on March 26, 1997. Magnetic declination: 20°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

RECEIVED BY
Umatilla County Surveyor
Date 4-97
Rec'd By KK
No. 97-76-R

Renews 6/30/97