

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


U-15

History of original corner establishment:

U.s. Cadastral Surveyors, under special instructions Group Numbers 350 and 643, set a 2 1/2" X 28" iron post with a brass cap marked:

Post was 14" in the ground, in a mound of stone. From the corner:

S 1/16 | S 27
C
C
1968



A Pine, 17" dia., S49°E, 42 lks.
A Pine, 13" dia., N61°W, 39 lks.

Description of corner evidence found:

I found a 2 1/2" iron pipe with a brass cap marked: Monument was in a mound of stone. From the corner:

S 1/16 | S 27
C
C
1968

A Ponderosa Pine, 16" dia., N67 1/2°W, 25.7 ft. with a healed blaze.
A Ponderosa Pine, 20" dia., S45°E, 27.7 ft. with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

BTs have blaze and a 6" band painted red, a BT tag and a "Land Survey Monument" sign. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 1/2°E.

Nov. 1, 1986



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 12-11-86
Rec'd By KA
No. 86-134-M

GPO-798-276