


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Record of the orig. survey states:
 History of original corner establishment: SET a BASALT STONE, 16 X 10 X 5, IN A MOUND OF STONE, SET BY RUFUS S. MOORE, US DEPUTY SURVEYOR, IN 1881, CONTRACT NO. 382. BRASS CAP SET BY BLM IN A DEPENDENT RESURVEY OF THE WEST BOUNDARY, T 6 S, R 32 E., WILLAMETTE MERIDIAN, OREGON, IN 1968.



BLM SURVEY FOUND NO REMAINING EVIDENCE OF ORIGINAL CORNER. SET AN IRON POST 28" LONG, 2 1/2" DIAM., 10" IN GROUND TO SOLID ROCK, IN A MOUND OF STONE, 4 FT BASE, TO TOP, WITH BRASS CAP MARKED: T 6 S, R 31 E, R 32 E, S. 36, S. 31, 1968.

FROM WHICH

- A JUNIPER 10" DIAM., BEARS N 30° E., 151 LKS DIST MKD. 1/4 S. 31 BT 1968
- A JUNIPER 8" DIAM., BEARS S 44° W., 100 LKS. DISP MKD. 1/4 S. 36 BT 1968

Description of corner evidence found: 3/4" BLM BRASS CAP SET ON 2 1/2" IRON POST SET IN MOUND OF STONE, MKD: T 6 S, R 31 E, R 32 E, S. 36, S. 31, 1968

FROM WHICH

- A JUNIPER 15" DIAM., BEARS N 25° E., 124.10 FT. (RECORD N 30° E., 151 LKS) WITH AN X SCRIBED ON FACE
- A JUNIPER 15" DIAM., BEARS S 53° W., 47.74 FT. (RECORD S 44° W., 100 LKS) WITH AN X SCRIBED ON FACE

Description of monument and accessories established to perpetuate the original location of this corner: EXISTING BEARING TREES (TWO JUNIPERS) WERE RESURVEYED FROM CORNER POINT AND ACTUAL BEARINGS AND DISTANCES NOTED AND ATTACHED USING US FOREST SERVICE BEARING TREE SIGNS (54-3), SURVEY MONUMENT SIGNS (54-9) WERE ATTACHED AND 6" RED BANDS PAINTED AROUND EACH TREE. ESTABLISHED BEARING OBJECT, A 3" X CHISELED INTO A 3' X 4' ROCK FACE OUTCROP, BEARS S 75° E., 57.96 FT. ALONG WITH X CHISELED W 1/4 36 | 31.

DROVE A STEEL GUARDPOST, S. 0° W., 4 FT. DIST., WITH 54-2 AND 54-9 SIGNS ATTACHED. (4th witness)
 MAGNETIC DECLINATION USED AT THIS CORNER TO ESTABLISH BEARINGS: D₆; 19° E.

WITNESS: KEN BATES, SCOTT KRIKA

I HEREBY CERTIFY THE ABOVE CORNER POINT WAS PERPETUATED IN OCTOBER '90. THRU JANUARY '91, AS HEREON DESCRIBED.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Guy W. Streamer

OREGON
 SEPTEMBER 23, 1977
 GUY W. STREAMER, JR.
 1341


Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
David H. Kraus
 (COUNTY OFFICIAL) by..... (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 3-91
 Rec'd By KA
 No. 91-22-R

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-1

History of original corner establishment: Record of the original survey states: Set a basalt stone, 16x10x5, in a mound of stone, set by Rufus S. Moore, US Deputy Surveyor, in 1881, contract no. 382. Brass cap set by BIM in a dependent resurvey of the west boundry T.6 S., R.32 E., Willamette Meridian, Oregon, in 1968. BIM survey found no remaining evidence of original corner. Set an iron post 28 in. long, 2 1/2 in. diam, 10 in. in ground to solid rock, in a mound of stone, 4 ft. base, to top, with Brass cap marked: T 6 S R 31 E R 32 E 1/4 S.36 S. 31 1968 From which: A juniper, 10 in. diam., bears N 30° E , 151 lks dist., mkd. 1/4 S 31 BT 1968. A juniper,, 8 in. diam., bears S 44° W , 100 lks dist., mkd. 1/4 S 36 BT 1968.



Description of corner evidence found: 3 1/4" BLM Brass Cap set on 2 1/2" iron post set in a mound of stone, mkd.: T 6 s R 31 E R 32 E 1/4 S 36 S 31 1968 From which: A juniper, 15" diam., bears N 25° E , 124.10 ft. (N 30° E , 151 lks) X scribed on face. A juniper, 15" diam., bears S 53° W , 47.74 ft. (S 44° W , 100 lks) X scribed on face.

Description of monument and accessories | established to perpetuate the original location of this corner: BT's resurveyed from corner point and actual dist. and bearings noted and attached using US Forest Service BT signs (54-3). Survey monument signs (54-9) were attached and a 6" red band painted around trees. Set bearing object, A 3" X chisled into a 3'x 4' rock outcrop, bears S 75° E , 57.96 ft. Chisled 1/4 36|31 Drove a 2 1/2" iron pipe with brass washer mkd. 1341 18" in ground to solid rock, bears S 0° E , 4 ft. dist. Magnetic declination used at this corner to est. bearings: De; 19° E.

Witness: Ken Bates

I hereby certify the above corner point was perpetuated in October 1990 thru March 1991, as hereon described.

REGISTERED PROFESSIONAL LAND SURVEYOR

Guy W. Streamer

OREGON SEPTEMBER 23, 1977 GUY W. STREAMER, JR. 1341

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 5-91 Rec'd By [Signature] No. 91-22-R