


History of original corner establishment:
 This corner was originally established by Frank W. Campbell, under Contract No. 468 dated April 12, 1883. The notes state that at the corner a 14x12x8" notched stone marked CC was set for the corner from which:
 a 10" Pine bears S29°E 37 lk (24.4 ft) marked T6S R33E S2 BT
 A 6" pine bears S8°W 38 lk (25.1 ft) marked T6S R33E S3 BT
 Stand corner. S33 | S34 bears West 47 lk (31.0 ft)



Description of corner evidence found:

Found a 3/4" iron pipe next to 14"x12"x8" stone with some visible notches on side - stone is loose. This pipe monuments the closing corner and was established from existing evidence by BLM in 1968. From the brass cap set as the closing corner, .20' south of pipe:
 A 7 1/2" standing dead lodge pole pine bears S62 1/2°E a distance of 36.5 feet scribed T6S R33E S2 CCBT
 A 9" standing dead lodge pole pine bears S82 1/2°W a distance of 17.3 feet scribed T6S R33E S3 CCBT (these are not original BT's). Corner is 2' west of a 3 way fence intersection.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner position a 2 inch by 30 inch iron pipe, with brass cap makred as shown, was set 20 inches in the ground and surrounded with a mound of stones to the cap. The brass cap was set at the intersection of the 1st standard parallel line and the closing line common to sections 3 & 2. The brass cap is located South 0.20 feet from the 3/4" iron pipe closing corner. Set steel fence posts on section lines south & west of corner and attached signs 54-2 to both posts and sign 54-4 to 1 post. Established 2 new BT's:
 A 8 1/2" tamarack bears S48 1/2°E 95.9 ft scribed T6S R33E S2 CCBT
 A 7" red fir bears S8°W 87.8 ft scribed T6S R33E S3 CCBT
 New BT's have a lower blaze scribed BT with a brass washer scribed PLS 1106 nailed flush. Attached signs 54-3 and 54-4 and painted red ring around all BT's above upper blaze. Measurements are to brass cap set.
 Used steel tape and magnetic compass with 19 1/2° east declination. Measured to center of BT's. See map of survey.


This corner set 11-20-79.

Witnesses: Bob English
 Clint Kelly

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106



Office of County Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the day of 19

..... by
 (COUNTY OFFICIAL) (DEPUTY)

A-17

RECEIVED BY
Umatilla County Surveyor
 Date 12-5-79
 Rec'd By ymjj
 No. A-1223-B
corresponding drawing