

USDA-FOREST SERVICE


Index File No. A-17
 T 6S R. 33E
 Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. S3 Cor. No. NE (C.C.)
 R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3/4" iron pipe next to 14"x12"x8" stone with some visible notches - stone is loose. This pipe monuments the closing corner and established from existing evidence by BLM in 1968.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 7 1/2" standing dead lodge pole pine bears S62 1/2° E a distance of 36.5 ft scribed T6S R33E S2 CCBT. A 9 inch standing dead lodge pole pine bears S82 1/2° W a distance of 17.3 ft scribed T6S R33E S3 CCBT. (these are not original BT's) measurements to brass cap set.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the location poster on tree on the west side of the road south of Neeeyes Creek the corner is 1270 ft + West. The standard corner for the SW corner section 34 bears west 29.50 feet. Corner is 2' west of a 3 way fence intersection.

Signature William R. Webb

Title PLS

Division _____

Headquarters _____

Date 11-20-79

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2" x 30" iron pipe 20" in ground with mound of stone. Cap is marked: The brass cap was set at the intersection of the 1st standard parallel line & the closing line common to sections 3 & 2. The brass cap is located south 0.20 ft from the 3/4" iron pipe closing corner. Set steel fence posts on section lines south & west of corner and attached sign 54-2 to both posts and sign 54-4 to 1 post.

T5S	R33E
S3	S2
CC	
T6S	R33E
1979	
PLS 1106	

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Established 2 new BT's:

A 8 1/2" tamarack bears S48°E 95.9 ft scribed T6S R33E S2 CCBT

A 7" Red Fir bears S8°W 87.8 ft scribed T6S R33E S3 CCBT

New BT's have a lower blaze scribed BT with a brass washer scribed PLS 1106 nailed flush.

Attached signs 54-3 and 54-4 and painted red ring around all BT's above upper blaze. Measurements are to brass cap set.

10

Work Done By William R. Wells Title PLS Date 11-20-76 State Registration No. 1106
 or Agency
 Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor's Office Date _____

11

REMARKS

Witnesses: Bob English
 Clint Kelly

Index File No.
 A-17

T
 6S

R
 33E

M
 Willamette

Tract or Surv. No.
 S3

12
 Cor. NE (C.C.S.)
 U.S. G.P.O. 1977-725-576/586