


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

*assumed
N 1/4 V-7*

History of original corner establishment:

This corner was set at proportionate position in 1968 by B.L.M. Cadastral Surveyor. The B.L.M. records state:



Set an iron post 28" long 2-1/2" dia. 21" in the ground with brass cap from which:

Lodgepole pine 8" dia. bears S42°E 12.9 feet.
Lodgepole pine 10" dia. bears S40°W 24.8 feet.

Description of corner evidence found:

Found standard B.L.M. pipe and brass cap exposed 6" in a mound of stone. Tamarack 8" dia. bears S39°36'W 27.7 feet (record Lodgepole pine 10" bears S40°W 24.8 feet).

Description of monument and accessories I established to perpetuate the original location of this corner:

I mark a Tamarack 6" dia. which bears S28°53'E 87.8 feet to center of tree at the lower blaze in which I place a brass washer stamped L.S. 1679.

I hereby certify the above corner accessories were measured as herein described on October 29, 1980.

Witness: Lloyd R. Smith
Tom Fasel



Office of..... Surveyor..... County of..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 4th day of March, 1981
 by David Drumbin (COUNTY OFFICIAL) by Betty Shatto (DEPUTY)

V-7

RECEIVED BY
 Umatilla County Surveyor
 Date 3-4-81
 Rec'd by BLS
 No. B-9-M