


E-7

History of original corner establishment:

Original Survey by Frank Campbell, under Contract No. 468, April 12, 1883, Set a Pine post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on N face, from which:
A Pine, 6 ins. dia. bears N14°W 14 lks. dist., marked 1/4 S BT.
A Pine 8 ins. dia. bears S60°E 18 lks. dist., marked 1/4 S BT.



Description of corner evidence found:

No evidence of the original corner or accessories was found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the proportionate position determined by survey between the NE corner and the NW corner of Section 7, T6S R33E, we set a 2"x 30" aluminum pipe, 26" in the ground, with aluminum cap attached, marked:

from which we mark new BT's:

An 8" White Fir, scribed "1/4 S6 BT" on a double blaze bears N18°E 28.1 feet,
and A 12" Douglas Fir, scribed "1/4" S7 BT" on a double blaze, bears S72°E 19.2 feet.

T6S R33E
1 S 6
4 S 7
PLS 1099
1984

Attached brass washer, marked "LS 1099" to lower blaze of new BT's.

Corner is located 22 ft. north of an east-west fence.

Compass Declination
Steel Tape

August 2, 1984

Witnesses:

Gary Langlitz, LS 1099
Ray Crapo
Greg Orton



Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 20th day of October, 1984
David Kauffman by Betty Cochran
(COUNTY OFFICIAL) (DEPUTY)

E-3

84-152-R