

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-1

History of original corner establishment:

Original Survey by Frank Campbell, Contract 468, dated April 12, 1883.

Set a basalt stone 12x8x6 ins., 8 ins. in ground for 1/4 sec. cor. marked 1/4 on N. face, from which:

- A Spruce, 10 ins. dia. bears S58°E 10 lks. dist. marked 1/4 S BT
- A Spruce 10 ins. dia. bears N38°E 11 lks. dist., marked 1/4 S BT



Description of corner evidence found:

Found the remains of the original SE bearing tree, an 18" Engleman Spruce, dead and down, we open and find good scribing "1/4 S"

No evidence of the corner stone or orig. N.E. bearing tree was found.

Description of monument and accessories I established to perpetuate the original location of this corner:

The original corner position is determined at record bearing and distance from the standing position of the original SE bearing tree.

At the corner position, we set a 2"x30" galvanized iron pipe, 22 inches in the ground and in a 2 ft. diameter mound of stone, with brass cap attached, marked:

from which:

- The original SE bearing tree, An 18" Engleman Spruce, dead and down, bears S58°E 6.6 feet
- And new bearing trees:
  - An 8" Engleman Spruce, scribed "1/4 S5 BT" on a double blaze bears N59°E 33.3 ft.
  - A 10" Grand Fir, scribed "1/4 S8 BT" on a double blaze, bears S 49°E 52.6 ft.

T6S R33E  
 $\frac{1}{4} \frac{S5}{S8}$   
 PLS 1099  
 1984

Attached brass washer marked "LS 1099" to lower blaze of each new bearing tree. Corner is located in E-W fenceline, approx. 15' west of creek, course north.

Compass Declination  
Steel Tape

August 1, 1984

Witnesses:

Gary Langlitz, LS 1099  
 Ray Crapo  
 Greg Orton



Office of Surveyor County of Umatilla  
 State of Oregon I hereby certify that the within instrument was filed in this office  
 for record on the 10th day of October, 1984  
David Krumbein by Betty Cochran  
 (COUNTY OFFICIAL) (DEPUTY)

E-7