


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established



Description of corner evidence found:

None



Description of monument and accessories established to perpetuate the original location of this corner

North Fork John Day Wilderness. North Fork John Day Unit. Point Number 432:

This point is located approximately on the township line between T 6 and 7 S on the east 1/2 mile of sections 1 and 36, R 33 E.

At a point on the ridge top as described in the wilderness boundary description, set a 2 1/2 inch by 30 inch flared aluminum pipe 24 inches into the ground with a 3 inch aluminum cap attached. The cap is marked as shown in the diagram above. From which:

- An 11 inch Western Larch bears N 54° W, 65.5 feet.
- An 8 inch White Fir bears S 2° W, 24.7 feet.

Both trees are scribed "WB/432 BT" on a single blaze and have a 3/4 inch brass washer, marked "PLS 1636", nailed flush to the lower portion of the blaze. Both trees have a "Bearing Tree" sign and a "Land Survey Monument" sign attached.

I hereby certify the above wilderness boundary corner was established as hereon described on July 6, 1989. Witness: Lynn McNamara. De: 20° E.

Office of County Surveyor \_\_\_\_\_ County of Umatilla  
 State of Oregon \_\_\_\_\_, I hereby certify that the within instrument was filed in this office  
 for record on the 13<sup>th</sup> day of September, 1989  
David H. Krumboltz by Dennis L. Gaylord  
 (COUNTY OFFICIAL) (DEPUTY)

Date 9-89  
 Record PL  
 No. 89-87R