


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established



Description of corner evidence found:

None

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Description of monument and accessories I established to perpetuate the original location of this corner:

North Fork John Day Wilderness, North Fork John Day Unit, Point Number 455

This point is located in the SE 1/4 of section 36, T. 6 S., R 33 E.

At a high point on the ridge between Winom Creek and Upper Long Meadows, Elevation 5652 feet, as described in the wilderness boundary description. This point is the top of a basalt boulder which is 12 feet by 7 feet by 2 feet high. The boulder is flat on top and at a point 1.5 feet from the southeasterly edge and 5.1 feet from the northeasterly edge, I mark an "X" at the corner point. From which:

An 8 inch Douglas-fir bears N71° W, 11.3 feet.  
An 8 inch Juniper bears N 42° E, 37.7 feet.

Both trees are scribed "WB/455 BT" on a single blaze and have a 3/4 inch brass washer, marked "PLS 1636", nailed flush to the lower portion of the blaze. Both trees are additionally signed with "Bearing Tree", "Land Survey Monument" and 27-6a, "National Forest Wilderness", signs.

I hereby certify the above wilderness boundary corner was established as hereon described on June 26, 1989. Witness: Lynn C. McNamara. De: 20° E.

Office of..... County Surveyor..... Umatilla  
Oregon..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the 13<sup>th</sup> day of September, 1989.  
*David H. Keumbert* by *Kathleen K. Knabsue*  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 9-89  
Rec'd By *KS*  
No. 89-58-R