


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established



Description of corner evidence found:

None



Description of monument and accessories established to perpetuate the original location of this corner

North Fork John Day Wilderness, North Fork John Day Unit, Point Number 467

This point is located in the northeast 1/4 of section 36, T. 6 S., R. 33 E.

At a point on the ridge between Winom Creek and Upper Long Meadow as described in the wilderness boundary description, set a 2 1/2 inch by 30 inch flared aluminum pipe, with a 3 inch aluminum cap attached, 25 inches into the ground. The cap is marked as shown in the diagram above. From which:

An 8 inch Lodgepole Pine bears S 55° W, 12.5 feet.

A 15 inch White Fir bears N 48° W, 14.6 feet.

Both trees are scribed "WB/467 BT" on a single blaze and have a 3/4 inch brass washer, marked "PLS 1636", nailed flush to the lower portion of the blaze. Both trees are signed with "Bearing Tree" and "Land Survey Monument" signs.

A non-system trail bears south approximately 50 feet. Course northwest - southeast.

Office of County Surveyor Umatilla  
Oregon  
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 13th day of September 1989 by David H. Kumberson (COUNTY OFFICIAL) by Kathleen K. Amberg (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-89  
No. 89-90-L