


R-5

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set a pine post 4 ft long 4 ins square 24 ins in ground for cor to secs 19, 20, 29 and 30 marked T6S S20 on NE, R33E S29 on SE, S30 on SW and S19 on NW faces with 2 notches on S and 5 notches on E edges from which:

- A Pine 12 ins dia brs N44°E 38 lks dist marked T6S R33E S20 BT
- A Tamarack 8 in dia brs S58°E 20 lks dist marked T6S R33E S29 BT
- A Fir 10 in dia brs S68°W 32 lks dist marked T6S R33E S30 BT
- A Pine 8 in dia brs N80°W 11 lks dist marked T6S R33E S19 BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

- Found remains of wood post 6 inches below the ground.
- Found a 14 inch diameter Ponderosa Pine N44°E, 25.1 feet, dead and down with scribes visible.
- Found a faint stump hole S58°E, approximately 13 feet.
- Found a 26 inch diameter White Fir S66°W, 23.6 feet, live and vigorous with blaze evident.
- Found a 10 inch diameter Ponderosa Pine N80°W, approximately 7 feet, dead and down, loose on the ground with scribes visible.

See map of survey dated August, 1987.

Description of monument and accessories established to perpetuate the

original location of this corner: In place of the found original post, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New BTs:

- A 23 inch diameter Douglas Fir bears N65°E, 15.58 feet marked T6S R33E S20 BT
- A 7 inch diameter White Fir bears S38°E, 36.94 feet marked S29 BT
- A 8 inch diameter White Fir bears N38°W, 23.81 feet marked X BT

I painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet North with 54-9 sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 11, 1987.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 27 day of August 1987
David H. Kumbelin by Kathleen K. Kumbelin
 (COUNTY OFFICIAL) (DEPUTY)

R-5

8747-C