

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


V-7

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set a granite stone 12x8x6 ins 8 ins in the ground for 1/4 sec corner marked 1/4 on N face from which;

A Pine 30 in dia brs S30°W 93 lks dist marked 1/4 S BT  
A Pine 24 in dia brs N85°E 46 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.  
Description of corner evidence found:

Found a granite stone 12x8x4 ins loose on ground 3 feet Southerly of corner position.

Found a 38 inch diameter Ponderosa Pine N90°E, 30.4 ft., live and vigorous with blaze evident.

Found a 30 inch diameter Ponderosa Pine stump S33°W, 61.4 ft., no marks visible.

See map of survey dated August, 1987.

Description of monument and accessories I established to perpetuate the

original location of this corner: At record distance from the found bearing trees, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 26" in the ground, from which:

New BT:


A 13 inch diameter Ponderosa Pine bears S29°W, 60.50 feet marked 1/4 S32 BT

Buried the original corner stone West and alongside of monument.  
Raised a mound of stone 3 ft. base to top of cap.

Set a steel fencepost approximately 5 feet West with 54-9 sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 9, 1987.

I painted a 6 inch red band around all bearing trees and attached 54-3 and 54-9 signs.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept. County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 29<sup>th</sup> day of August 1987  
David H. Lamberton by Kathleen Lamberton  
(COUNTY OFFICIAL) (DEPUTY)

87-420