


History of original corner establishment:

The original corner was established by Frank W. Campbell on July 1, 1883, under GLO contract No. 468, as follows: Set a post for the corner from which:
 A 30" pine bears N25° E, 27 links (17.82 feet).
 A 6" pine bears S22° E, 4 links (2.64 feet).
 A 8" pine bears S31° W, 15 links (9.9 feet).
 A 6" pine bears N18° W, 8 links (5.28 feet).
 Griffith was unable to recover evidence of the original corner, and on July 29, 1987, he established the corner by proportionate measurement. He set a 2 1/2" aluminum pipe with an aluminum cap attached which he marked as shown in the diagram above, from which: A 1" x 66" steel fence post set 50" in the ground bears N45° E, 10.15 feet. A 6" Western Larch bears S1° E, 13.21 feet. A 10" Western Larch bears S46° W, 15.09 feet. A 7" Western Larch bears N45° W, 47.55 feet.



Description of corner evidence found:

A 2 1/2" aluminum pipe with a 2 1/2" aluminum cap attached which is marked as shown in the diagram above. The cap is protruding 1" above the ground, from which:
 A steel fence post protruding 20" above the ground bears N51° E, 10.15 feet.
 A 7" Western Larch snag with double healed blazes bears S2° 45' W, 13.6 feet.
 A 11" Western Larch snag with burnt out double blazes bears S50° 15' W, 15.2 feet.
 A 8" Western Larch snag with double healed blazes bears N41° 15' W, 47.5 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

New references:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S33", attached at ground level, bears S53° 45' E, 63.1 feet.
 A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S32", attached at ground level, bears S43° W, 60.5 feet.
 A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S29", attached at ground level, bears N18° W, 73.6 feet.

I hereby certify the above corner was perpetuated as hereon described on March 25, 1997. Magnetic declination: 20° E.



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 4-97
 Rec'd By KK
 No. 97-77-R

V-9