

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or  
Survey No.

Cor.  
No. AP-132

R.D. NFJD  
N.F. UMATILLA

County UMATILLA  
State OREGON

**CORNER DIAGRAM**

AP-132



DESCRIBE CORNER MONUMENT FOUND  
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
NONE

**PHOTO IDENTIFICATION DATA**

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

**PLANE COORDINATE POSITION DATA**

State: Oregon Zone: North

X: 2,496,147.21'

Y: 516,333.81'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located on a high point on the ridge between an unnamed tributary of  
Hidaway Creek and Big Creek

*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, 12" in the ground surrounded by 3' by 11" high rock mound, marked "NFJD WILDERNESS TOWER UNIT AP-132 RLS2308 1993".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" Englemann Spruce, N. 21° W., 43.6 ft., mkd. "WB/132""BT" on double blaze.

12" Pine, S. 75° E., 42.6 ft., mkd. "WB/132"BT" on double blaze.

Work Done By: **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.:

AP-132