

Index  
File No.

**CORNER RECORD (SEARCH)**  
(Ref. FSM 6161.4)

Tract or  
Survey No.


**Tower Unit**

Cor.  
No. **AP-237**

**T. 6 S. R. 34 E.**  
**Merid. Willamette**

R.D. North Fork John Day      County Umatilla  
N.F. Umatilla                      State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

Found a 3 1/4" aluminum cap, set flush with the ground.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

20" Subalpine Fir Snag, N. 12 E., 12.5 feet, with scribing visible on double blaze.  
8" Subalpine Fir Snag, S. 87 1/2 E., 13.9 feet, with scribing visible on single blaze.

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the jct. Of roads 5226 and 5226-200 walk westerly and southerly on 5226-200 approx. 0.32 miles to the second switchback. The corner is located on the easterly edge of the switchback.

**PLANE COORDINATE POSITION DATA**

State:                      Zone:

X:

Y:

Datum:

Signature

**D. Schlaich**

Title

**Land Surveyor**

Division

Headquarters

**S.O.**

Date

**10/27/1997**

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

15" Grand Fir, S. 25 E., 16.7 feet, scribed "WB/237" "BT" on double blaze.  
9" Lodgepole Pine, SOUTH, 27.7 feet scribed "WB/237" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 10/27/1997 State Registration No. or Agency \_\_\_\_\_

Certified Corner Record Prepared? Yes  No  Filed At \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON


Tract or

Survey No. Tower Unit

Cor.

No. AP-237

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

NONE

**PHOTO IDENTIFICATION DATA**

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

**DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the jct. of FS rds. 5226 and 5226-200 walk westerly and southerly on 5226-200 approx. 0.32 miles to the second switchback in the road. The corner is located on the easterly edge of the switchback.

**PLANE COORDINATE POSITION**

State: Oregon Zone: North

X: 2,499,954.37'

Y: 510,491.07'

Datum: NAD1927

*Signature*

D. Schlaich

*Title*

Land Surveyor

*Division*

*Headquarters*

S.O.

*Date*

09-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 3/8" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS TOWER UNIT AP-237 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

20" Grand Fir, N. 16° E., 12.5 ft., mkd. "WB/237"BT" on double blaze.

7" Grand Fir, S. 80 1/4° E., 13.9 ft., mkd. "WB/237"BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No. T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-237