


CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

T. 6 S. R. 34 E.
Merid. Willamette

R.D. North Fork John Day County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar, with a 3 1/4" aluminum cap, projecting 6" out of a small stream bed.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

5" Western Larch Snag, S. 36 E., 27.2 feet, with burnt out double blaze.
3" by 1' high stub, S. 77 3/4 W., 15.8 feet, no marks visible.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5507 travel southeasterly on 52 approximately 0.41 miles. Then walk southerly approximately 200 feet to the head of an unnamed creek. Follow the unnamed creek downstream approximately 5400 feet to the corner which is located at the confluence of two unnamed creeks.

PLANE COORDINATE POSITION DATA

State: Zone:
X:
Y:
Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/22/1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 22" in the ground, N. 23 1/4 E., 20.5 feet.
RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, S. 75 E., 21.8 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/22/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

USDA-FOREST SERVICE

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

Tract or

Survey No. NFJD Unit


County UMATILLA

State OREGON

Cor.

No. AP-548

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5507 travel southeasterly on 52 approx. 0.41 miles. Then walk southerly approx. 200 feet to the head of an unnamed creek. Follow the unnamed creek downstream approx. 5400 feet to the corner which is set at the confluence of two unnamed creeks.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,475,201.77'

Y: 497,059.42'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the water surface, marked "NFJD WILDERNESS AP-548 RLS 2308 1993".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

5" Western Larch, S. 35° E., 27.2 ft., mkd. "WB/548" "BT" on double blaze.

4" Englemann Spruce, S. 77° W., 15.9 ft., mkd. "WB/548" "BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.
or Agency

Certified Cor. Report Prepared? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-548