


T. 6 S. R. 34 E.
Merid. Willamette

R.D. North Fork John Day
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5200-440 travel easterly on 52 approximately 0.37 miles. The corner is located 200 feet northerly of the road.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at a point 200 feet northwesterly of and perpendicular to the centerline of road 52 at the base of a ridge, a 5/8" by 36" rebar with a 3 1/4" aluminum cap, flush with the ground, stamped "NFJD WILDERNESS TOWER UNIT AP-568 RLS 2308 1997".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10" Douglas Fir, S. 45 W., 46.2 feet, scribed "WB/568" "BT" on single blaze.
14" Western Larch, N. 87 1/4 W., 44.1 feet, scribed "WB/568" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 09/1997 State Registration No. _____
or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS