


History of original corner establishment:

Corner originally established by Frank W. Campbell in July, 1883, under contract No. 468, as follows:

Set a sandstone 15" x 18" x 12", 10" into the ground marked 1/4 on the north face from which:

- A 20" Tamarack bears S31° E, 20 links (13.20 feet).
- A 20" Fir bears N31° W, 24 links (15.84 feet).
- Both marked "1/4S BT".



Description of corner evidence found:

Original 20" Tamarack is a 21" Western Larch with double healed blazes. Bears S31° E, 13.2 feet.  
 Original 20" Fir is down, decayed and burnt. Axe marks are visible on the charred face. Root hole bears N31° W, 15.84 feet.  
 No stone at the corner and no stone in the vicinity.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the original bearing trees, set a 2 1/2 inch by 30 inch aluminum pipe 27 inches into the ground with a 3 inch aluminum cap attached which is marked as shown in the diagram above... From which:

- A 7" Western Larch bears S48° W, 32.8 feet scribed "1/4 S28 BT".
- A 7" Western Larch bears N58° 30' W, 68.2 feet scribed "1/4 S21 BT".
- A 5" Western Larch bears N39° 30' E, 37.2 feet scribed "1/4 S21 BT".

Each new bearing tree is scribed on double blazes, has a 3/4" brass washer, marked "1636", nailed flush to the lower scribed face and has a 54-3, Bearing Tree sign nailed above the blaze and a 54-9, Land Survey Monument sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on June 23, 1993.

Magnetic declination: 20° E.

NAD1983 Geographic Position (+ or - 2 to 6 meters):  
 Latitude: 45-01-34.339 N  
 Longitude: 118-37-35.067 W

Witnessed by: Shane Sills and Trina Alden

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

Dennis L. Gaylord

**OREGON**  
JULY 14, 1978  
**DENNIS L. GAYLORD**  
1636

**EXPIRES 12/31/93**

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19....  
 by .....  
 (COUNTY OFFICIAL) (DEPUTY)

R-11

**RECEIVED BY**

Umatilla County Surveyor

Date 7-93

Rec'd By KS

No. 93-21-R