

File No. **V-09**

T. **6 S.** R. **34 E.**  
Merid. **Willamette**

**CORNER RECORD (SEARCH)**  
(Ref. FSM 5151.4)


R.D. **North Fork John Day**  
N.F. **Umatilla**

County **Umatilla**  
State **Oregon**

Tract or  
Survey No.

Cor.  
No.

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**  
NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**  
NONE

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By  
Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES; ALSO HOW TO REACH CORNER**  
The corner is located approximately 200 feet east of the Winom Creek campground, with the 24" Western Larch bearing tree being on the edge of one of the campgrounds campsite access roads.

**PLANE COORDINATE POSITION DATA**

State:            Zone:  
X:  
Y:  
Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at 2 1/2" by 30" aluminum pipe with a 3 1/4" aluminum cap, 20" in the ground, surrounded by a stone mound 1 1/2' in diameter by 10" high.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 23" in the ground, N. 42-21 E., 22.62 feet.  
RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, S. 47-05 E., 19.87 feet.  
24" Western Larch, S. 89 W., 196.0 feet, scribed "T6S R34E S32" "BT" on double blaze.  
RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 23" in the ground, N. 46-01 W., 21.01 feet.

Work Done By D. Schlaich Title Land Surveyor Date 09/1997 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_  
Certified Corner Record Prepared?  Yes  No Filed At: Umatilla County Surveyor's Office Date 11/1997

REMARKS