

2-15


History of original corner establishment:

Original Survey by Meldrum and Campbell
Contract No. 380, 1881.

Set a Pine Post for 1/4 Sec. Cor.

Pine 40 in. dia. bears N43°E 118 lks. Dist.

Fir 20" in dia. bears S55°W 29 lks. Dist.



Description of corner evidence found:

The remains of the original BT's.

A 26" Douglas Fir snag, previously opened, scribing "S" visible; and an approximate 20" Pine stump, rotten, no marks visible. No trace remains of the original Pine post corner monument. At the corner we find a 2 1/2" Iron Pipe, extending 6" above ground, with brass cap attached, marked: From which the remains of the original BT's:

A 26" D. Fir snag bears S55°W 19.1 ft., and a 20" rotten Pine stump bears N43°E 77.9 ft., and new BT's apparently marked by BLM. A 10" Douglas Fir, with scribing "1/4 S 34 BT" visible on a single blaze bears N6°E 45.9 ft. And a 12 Douglas Fir with scribing 1/4 S3 BT" visible on a single blaze bears S80°E 30.7 ft.

U.S. Dept. of the Interior
Bureau of Land Management

T6S R31E

1/4 S34
S3

T7S

1980

Description of monument and accessories established to perpetuate the original location of this corner:

Staff Compass & Steel Tape

Declination 19°East

July 29, 1982

Witnesses: Gary Langlitz
Greg Orton
Jeff Anderson



Office of Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 18 day of January, 1983
David H. Kline by _____
(COUNTY OFFICIAL) (DEPUTY)

2-15

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd by _____

l.o. 03-03-B