

Index

File No. C20

T 7S R. 31E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor.
No. _____

R.D. N.F. John Day County Grant

N.F. Umatilla State Oregon

CORNER DIAGRAM

T7S R31E

E 1/16

C-----C

S2

1993

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is 300 feet Northeast of the Fixit Shop in Dale

Signature

Willie R. Wells

Title

PLS

Division

Headquarters

Pendleton, OR

Date

1/19/94

7100-52-(3/68)

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

A 2½" aluminum cap on 2½"X30" aluminum pipe, 22" in ground with mound of stone to cap, marked as shown in corner diagram. Attached sign 54-2 and 54-9 to steel fence post set 4.0 feet West of monument.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 14" ponderosa pine bears N4½°W-99.7 feet, scribed: CE 1/16 S2 BT.
A 21" ponderosa pine bears S68°W-171.1 feet, scribed: CE 1/16 S2 BT.
New bearing trees have a brass washer stamped "PLS 1106" nailed to face of blaze. Attached sign 54-3 and 54-9, painted face of blaze and a 6" red band around each bearing tree.

Work Done By. WR Wells Title PLS Date 8/27/93 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: GRANT CO. SURVEYOR'S OFFICE Date 1/94

REMARKS

This corner was established as part of a USFS contract.

Index File No. C20 T. 7S R. 31E M. Willamette Tract or Surv. No. Cor. 13